

# Current and Planned High Proton Flux Operations at the FNAL Booster

Fernanda G. Garcia  
Fermilab

52<sup>nd</sup> ICFA HB2012  
September 17-21, 2012



# Outline

- Overview of Booster performance over the past decade
- Got protons? More, more and more protons...
  - Proton Improvement Plan
    - improvements on
      - beam loss control
      - collimation
      - shielding
- Summary

# Introduction to FNAL Booster Synchrotron

- H<sup>-</sup> ions are stripped and multi-turn injected onto the Booster
- Protons are accelerated from 400 MeV to 8 GeV in 33 msec
- Fast cycling synchrotron
  - Fast magnet ramping
  - Frequency of 15 Hz
- Single turn extraction


Booster	
Circumference (m)	474
Harmonic Number	84
Kinetic Energy (GeV)	0.4 - 8
Momentum (GeV/c)	0.954 - 8.9
Revolution period (μsec)	$\tau_{(inj)}$ 2.77 – $\tau_{(ext)}$ 1.57
Frequency (MHz)	37.9 - 52.8
Batch size (ppp)	4.5 E12
Focusing period	FDooDFo
N <sup>o</sup> focussing periods	24




# Proton Throughput

- Neutrino program demands lots of protons delivery to target
  - prompted by MiniBooNE and NuMI experiments
  - Booster accelerator performance improved tremendously for the past decade to meet the laboratory programmatic goals
- The future laboratory experiments that are either under construction or in DOE CD-process demands another factor of 2 for the next several years
  - doubling the proton flux by increasing the number of cycles with beam
    - 8 GeV @ ~ 10 kW for Booster Neutrino Beam (BNB) experiments
    - 8 GeV @ ~ 50 kW for 120 GeV Neutrinos at Main Injector (NuMI) experiments
    - 8 GeV @ ~ 20 kW for Muon production (Muon Campus experiments)
- Continue increase demands on the Proton Source threaten reliable operation due to rely on components that are either no longer commercially available or are at risk of being discontinued

# Historical beam throughput in Booster




# FNAL Proton Source 2000 – 2012 Timeline



# Standard Booster Loss Profile



## Normalized beam losses




Data show beam losses for three beam cycles

Pbar production 4.5E12 ppp  
 MiniBooNE 4.5E12 ppp  
 NUMI 4.1E12 ppp

## Power loss & radiation survey



# Booster in the Intensity Frontier Era



# Proton Improvement Plan - PIP

FNAL Accelerator Associate Director set the direction in Dec'10:

*The **Proton Improvement Plan** should enable Linac/Booster operation capable of*

- deliver  $2.2E17$  protons per hour (at 15 Hz) in 2016*
- while maintaining*
- Linac/Booster availability > 85%, and*
- residual activation at acceptable levels*

*and also ensuring a useful operating life of the proton source through 2025.*

S. Henderson


➤ The scope of the **PIP** includes

- increase Booster repetition rate by upgrading (or replacing) components
- replacing components that have poor reliability
- studying beam dynamics to diagnose performance limitations

# FNAL Proton Source



## Looking into the Future

### 2013 and beyond




# Aperture Improvement : Removal of L13 Extraction Region


- Beam is extracted from Booster in a dogleg configuration
  - DC vertical dipoles work with 3-bump (BEXBUMP)
- In the old days, Booster had two extraction regions
  - L13: old extraction region to Main Ring
  - L3: present extraction region to Main Injector (MI)



- L13 septa remained in place for operation with MI
  - septa obstructed top part of the aperture
  - vertical acceptance at 400MeV was  $\frac{1}{2}$  of otherwise available
  - increased complexity on tuning to extract at L3
  - increased downtime due to components failure with the increase in radiation
- Overall gains
  - beam throughput in the range of 15-18%
  - reduce an important localized high loss





Booster Radiation Increases from May 6 2004 to Mar 14 2007




# Booster Orbit Control Improvements Magnet Move

Contribution by K. Seiya

- Improve acceptance with goal of reducing beam loss
- Two magnets were realigned prior to 2012 shutdown as a bench test to verify procedure





After alignment...




Difference of the measured orbit between before and after magnet move is  $\sim \pm 2$  mm.

Measured aperture before (left) and after (right) the magnet realignment.




# Present Booster Notch System



Extraction kicker has rise time of  $\sim 40$  nsec



Bucket spacing at extraction energy  $\sim 19$  nsec



- Beam lost during extraction
  - 3 batches  $\sim 200$  J
- Notch is created by kicking the beam vertically at L5 @ 2 different cycle times
  - 400 MeV ( $\sim 0.4$  ms) (un-cog events)
    - Reduce losses down to 5%
  - 700 MeV ( $\sim 7$  ms) (cog events)
    - Reduce losses down to 9%
- About 87% of beam is removed from the bucket
  - most of particles are intercepted by magnet pole tips. Major concern!
  - remaining beam is “nocked” at L12 into L13 absorbers
- Booster has never lost a magnet, but radiation is noticeable







# Future Booster L13 Notching & Absorber

## ➤ PHASE I: Notcher Relocation

- Abort gap is created using 3 long kickers located at L5
- Beam is kicked **horizontally** into new absorber at L13
  - Notching efficiency increased by ~ 10%
  - Notching cycle time will remain unchanged

## ➤ Beam will be deposited at a new absorber



Present configuration

## ➤ Absorber elements

- stainless steel vacuum liner
- steel absorber blocks
- concrete blocks
- not shown
- polyethylene masks
- marble to further shield the personnel corridor aisle




## ➤ Radiation concerns

- ALARA for personnel
- sump water
- beam-on radiation in the gallery

# Present Booster Cogging System

- Booster beam has a notch
- Extraction is timed to coincide with the notch
  - synchronized to the beam already in the Main Injector
- Synchronization obtained by manipulating the radial position
  - change beam's velocity and beam path
- Required for multiple batch operation in MI
  - pbar production for Run II and NuMI
  - essential for slip-stacking operation in MI


## Multi-batch "2+9" Operation Scheme



- Notch in cog events is delayed ~ 7 ms after injection
  - induce higher regular losses (20 J/notch @ 700 MeV)
  - major concern going to higher repetition rates
- Typical horizontal position vary +/- 6 mm
  - RF frequency cogging complicates the setup of beam collimation scheme due to radial orbit changing

# Future Booster Cogging System

- Extract 12 pulses every 15Hz for the NOvA operation
- New Booster correctors allow for magnetic cogging
  - Dipoles are much stronger than previous corrector package



$$\frac{\Delta f_{rev}}{f_{rev}} = \frac{1}{\gamma^2} \frac{\Delta P}{P} - \frac{\Delta L}{L}$$

$$= \frac{1}{\gamma^2} \frac{\Delta B}{B}$$



Contribution: K. Seiya

Fixed with RPOS feedback


Changed by dipole corrector

## Benefits


- Keeps the orbit centered
  - saves aperture
- Stronger at the start of the cycle
  - allows notch in cogging events to happen earlier in the cycle
  - reduces beam power loss
  - makes notch outside Booster possible



Recycler





Mai Injector




[buckets/μmsec]

# Present Booster Collimators

- Designed to be a 2-stage beam collimation system
  - enforce strict aperture in a location
  - high amplitude particles are intercepted by a thin primary foil
  - subsequently absorbed by thick stainless steel secondary collimators



- Collimation system absorbed radiation from uncontrolled beam losses in a location that can be well shielded




- Collimation system has not been operated as designed
  - the primary collimator is retracted
  - secondary collimator positions (H&V) are optimized to cope with radial orbit variation inherited in the RF coggling system

# Present Booster Radiation Protection Scheme

## Above ground radiation protection scheme

- Additional steel installed above the L3 extraction region
- Notch beam was established
- Concrete shelf installed inside both East and West Booster towers
- Collimation system absorbed radiation from uncontrolled beam losses in a location that can be well shielded
- Array of 50 interlock radiation detectors covered all loss points around the ring
  - trip set point based on the occupancy of the area it is protecting




## Tunnel activation protection scheme

- Beam losses cause activation of accelerator components
  - potential to lead to equipment failure
  - long down times due to the need to restrict doses to personnel
- Operational efficiency demands that high maintenance components (e.g. RF cavities) have stricter limits
- Array of 60 beam loss monitors (BLMs) control losses locally
  - each BLM has a device which measures the total loss sum over the past 100 sec


# Future Booster Radiation Protection Scheme

Booster shielding was assessed in 1998

Accelerator Shielding Envelope	1.8E17 p/hr
Operational limit	1.22 E17 p/hr
Warning Limit	1.09 E17 p/hr



- The main concern is improving shielding in the 182 single-leg penetrations
  - currently filled with 12 feet of polyethylene beads
  - Desire: 5 mrem/hr at the top of penetrations



Courtesy: I. Rakhno

1 mSv/hr=100 mrem/hr

- The most penetrating radiation component is neutrons.
  - Detailed description of neutron interactions with matter was used in these simulations by means of MCNP mode in MARS code
- Work continues to identify the best solution

# Summary

- To continue to support Fermilab program operation through 2025 Proton Source will need additional improvements
  - *Proton Improvement Plan flux goal will double present running conditions*
    - ensure continuity of operations in the face of potential delays for Project X
    - The PIP is currently underway and will be completed in 2018

